BSA
Consulting Engineers, PLLC
Firm Reg. #F-4415

PLAINVIEW ISD HIGH SCHOOL RENOVATIONS AND ADDITIONS
PLAINVIEW, TEXAS
BSA Project No. 10-090

STATE OF TEXAS
CARL W. WAMPLER
97056
LICENSED
PROFESSIONAL ENGINEER
8-22-11

ADDENDUM NUMBER ONE

August 22, 2011

NOTICE TO BIDDERS:
The following shall be incorporated in and become a part of the original Drawings and Specifications of the above identified project. Please acknowledge receipt of this Addendum by noting it on your Proposal.

Mechanical Items:

Item 1: In the Specifications, Section 15500, add the following to 1.1-A:

"The new fire line to the building and fire riser assembly shall be sized to accommodate the addition of the remainder of the High School to the fire sprinkler system at a future date (outside the scope of this project). The total floor area of the building anticipated for addition in the future is 125,000 square feet."

End of Mechanical Addendum