BSA
Consulting Engineers, PLLC
Firm Reg. #F-4415

PLAINVIEW ISD HIGH SCHOOL RENOVATIONS AND ADDITIONS
PLAINVIEW, TEXAS
BSA Project No. 10-090

08.22.11

STATE OF TEXAS
MICHAEL T. STRAHAN
84881
LICENSED
PROFESSIONAL ENGINEER

ADDENDUM NUMBER ONE

August 22, 2011

NOTICE TO BIDDERS:
The following shall be incorporated in and become a part of the original Drawings and Specifications of the above identified project. Please acknowledge receipt of this Addendum by noting it on your Proposal.

Electrical Items:

Item 1: On the drawings, Sheet E001:
1. In the Light Fixture Schedule Add Fixtures 'J1'. Type 'J1' shall be Recessed Portfolio Model # C9257EEM-I420-9350LI
2. In the Light Fixture Schedule Add Fixtures 'J2'. Type 'J2' shall be Recessed Portfolio Model # C9242E-9211LI

Item 2: On the drawings, Sheet E201:
1. Omit Keyed Note # 3 and the panel it references.
2. Revise Keyed Note #4 to read as follows: "EXISTING PANEL TO BE REMOVED AND REPLACED. ALL EXISTING BRANCH CIRCUITS TO REMAIN AND BE RECONNECTED TO NEW PANEL."

Item 3: On the drawings, Sheet E215:
1. In The Electrical Riser Diagram revise the feeder size serving Existing Panel "A" to (4) #250MCM & #6 GR. in 2-1/2" C. Approximate feeder distance 750 ft.

Item 4: Include in this Addendum Attached Supplemental Drawings E408A and E409A.

End of Electrical Addendum