August 23, 2011

ChapmanHarvey
ARCHITECTS, INC.

REGISTERED ARCHITECT
LENORA K. CLARDY
TEXAS
8/23/11

Plainview ISD
Plainview High School Renovation and Addition
Plainview, Texas

Bid Date: August 31, 2011 (*note item #1)
Bid Time: 2:00
Bid Location: Southwest General Contractors
223 SW 4th
Amarillo, Texas 79101

Addendum 1

The following shall be incorporated in and become a part of the original Drawings and Specifications of the above identified project.

Attached:
Electrical Addendum 1
Sheets E408A and E 409A
Mechanical Addendum 1

Architectural Items:

1. Bid date is changed from Tuesday, August 30, 2011 to Wednesday, August 31, 2011. Time and location remain unchanged.

2. Omit paragraph 3.4.4.2 from the AIA document A201. It will be the responsibility of the Contractor to ensure compliance with the prevailing wage requirements of the Texas Government Code, Chapter 2258.

3. Omit section 07 9500 from the specifications.

4. On sheets CS103 and CS104 - Omit the requirement for 1 hour fire separation between Phases 2 and 3 and Existing classrooms. No Fire separation is required at this location.

5. Omit Section 08 1173 from the specifications and omit door 3.252 from the project.

6. Sheet A207 - Add door 2.209 to Door Schedule for Phase II found on. Door is similar to Door 2.213 in all respects with the exception of swing and is to swing into Secretary 2.209. Hardware for this door is included under the heading of Hardware Set 20.

7. Add Curved Security Grill similar to the grill outside of the Student Lobby 1.101 directly above on Second floor outside of Library 1.201. - See supplemental drawing 1

8. Provide a unit price for 10'-6" x 10'-0" Security Grill. Include installation and required overhead support. Location and number of Security Grills will be provided upon acceptance of pricing.

9. Glazing configuration on towers is to be changed to reduce span height from 16'-4" to that shown in supplemental drawing. Elevations of HSS supports are to change as shown and contractor is to add additional framing at top of the storefront system as shown. - See supplemental drawing 4 and 5

10. Section 11600 - Omit 3.4 items F and G - no Set-up tables or Student Desks are to be included in the contract.

612 Broadway
Lubbock, Texas 79401
806.749.1153 fax 749.1866
architect@chapmanharvey.com

11. Section 11600 - Change 2.5 D to read, "Provide black epoxy resin *endsinks* . . . "

12. Items 12 and 13 are markerboard and tackboard respectively. All classrooms are to receive markerboard / tackboard combinations with the dimensions shown on sheet A219. Science labs are to receive 6'-0" markerboards with 4'-0" tack boards in lieu of the 4'-0" markerboards shown in science lab elevations.

13. Section 08 7100 - Door hardware Schedule included in specifications to be replaced with reformatted version attached.

14. All references to sheet CS2 shall be changed to CS102, which is a Texas Accessibility Standards information sheet.

15. At new column locations in the basement - carefully cut a square from the existing carpet large enough for the placement of the footing and protect the existing carpet from soiling and / or damage during construction. Upon completion of the installation of the new columns, install carpet in the void of equal make and quality in an accent color to be selected by architect from manufacturers standard color.

16. New columns in basement are to be left exposed and are to be primed and painted. Color to be selected by architect.

17. At new column locations in the basement - ceiling is to be reworked using the existing suspended ceiling system.

18. Add shelving to storage rooms 2.220a, 2.220b, 2.219a, and 2.219b. Shelving layout to be similar to Storage 2.108a.

19. Sheet A213 - omit note R46 and replace with note C2 - finished gypsum wall board furrdown.

20. Keyed notes for sheet A214 to be similar to sheet A213.

21. A minimum slope of 1:12 shall be provided at skylights. Revised detail will be provided.

22. Skylight manufacturer may provide alternative pricing for rectilinear skylights sized 20'-0" x 4'-0". If pricing for rectilinear skylights is accepted, revised reflected ceiling plan will be provided with new skylight locations. Quantity of skylights unchanged..

23. On sheet A105 - omit note R56.

24. On sheet A106 - note R1 should read cut metal letters as specified. Finish is to be selected by architect.

25. On sheet A106 - note R43 typ on existing wall to the north should be note R68 - EXISITNG OPENING TO REMAIN OPEN FOLLOWING ABATEMENT. CONTRACTOR TO PROVIED PLASTIC LAMINATED WALL PANEL FINISH ON INSIDE FACES OF OPENINGS AND AS A REPLACEMENT FOR THE TILE SILL. UPON ABATEMENT, ARCHITECT WILL DETERMINE IF EXISTING OPENING SUFFERS IRREPARABLE DAMAGE FROM WINDOW REMOVAL AND CANNOT REMAIN UNFINISHED. PROVIDE UNIT PRICE FOR FINISH FRAMING AT OPENING.

26. See supplemental drawing 6 for elevation of existing opening treatment.

27. See supplemental drawing 7 for revised wall legend.

28. 9/A111 - cap stone to be 1'-1" not 2'-1 3/4" as shown.